

12. All operations conducted on the premises, including the warming up, repair, arrival, departure or running of trucks, earthmoving equipment, construction equipment and any other associated equipment shall be limited to the period between 7:00 A.M. and 5:00 P.M. everyday unless otherwise approved by the City of Coeur d'Alene.

13. All existing improvements including curb and gutter, sidewalks, asphaltic concrete or Portland Cement Concrete paving, which are being joined or matched in connection with this project shall be joined or matched in a manner satisfactory to the City Engineer, including necessary sawcutting, removal, and replacement.

14. No revisions shall be made to these plans without the approval of the City Engineer.

15. Compaction testing shall be performed on the following:

Embankment	-	1 per 50 cy
Trench	-	1 per 50 cy located in pipe zone, mid-depth, surface, and around manholes and valves.
Subgrade		
Road base	-	1 per 750-1000 sf
Asphalt paving		
Curb and gutter	-	1 per 75-100 lf
Sidewalk		

The City may require additional testing if deemed necessary.

16. The Contractor shall provide a copy of the percolation test results and a letter from the design professional stating that the swales were constructed in accordance with their recommendations.



CITY OF COEUR D'ALENE STANDARD DRAWING

GENERAL NOTES

PAGE 2

APPROVED BY:

Chris Bosley
CITY ENGINEER, PE 10804

7/24/26
DATE:

DWG NO.

M-23